



SIDE VIEW

END VIEW

**TANK: CATEGORY 4.** 4" 1350 GALLON 2 COMPARTMENT TANK REINFORCED WITH #3 REBAR 12" O/C. BOTH WAYS. 4" WALLS AND 4" BOTTOM. INLET AND OUTLET RESILIENT CONNECTORS PER ASTM-923-98. CONNECTORS MUST BE USED WITH APPROVED CLAMP. CONNECTOR WILL ACCEPT 4" PVC PIPE.

**LIDS:** 4" LID WITH 1-22" ROUND MANHOLE COVER AT EACH END OF TANK  
 8" LID WITH 1-22" ROUND MANHOLE COVER AT EACH END OF TANK  
 LID IS REINFORCED WITH GRADE 60 REBAR.

**TANK & LIDS:** 4000 PSI CONCRETE AT 28 DAYS

IMPRINTED ON INLET END OF TANK:

**LEGEND: FSI 1350 STATE APPROVAL NUMBER: 01-011-19D-C4**

**WEIGHTS:** TANK ONLY 9,800  
 TANK & 4" LID 12,774  
 TANK & 8" LID 15,748

THIS SEWAGE TREATMENT RECEPTACLE HAS BEEN DESIGNED, CONSTRUCTED AND STRUCTURALLY TESTED IN ACCORDANCE WITH CHAPTER 64E-6.013, FLORIDA ADMINISTRATIVE CODE, (FAC) DATED APRIL 28, 2010.

DRAWING NOT TO SCALE

<b>FLORIDA SEPTIC, INC</b> P.O. BOX 545 HAWTHORNE, FLORIDA 32640 (800) 940-8265	<b>MODEL:</b> 4" 1350 GAL. TANK	
	<b>REVISED:</b> 05/01/2011	<b>APPROVAL DATE:</b> 07/30/2001