



**SIDE VIEW**

**END VIEW**

**TANK: CATEGORY 4.** 4" 1500 GALLON 2 COMPARTMENT TANK REINFORCED WITH #3 REBAR 12" O/C. BOTH WAYS. 4" WALLS AND 4" BOTTOM. INLET AND OUTLET RESILIENT CONNECTORS PER ASTM-923-98. CONNECTORS MUST BE USED WITH APPROVED CLAMP. CONNECTOR WILL ACCEPT 4" PVC PIPE.

**LIDS:** 4" LID WITH 1-22" ROUND MANHOLE COVER AT EACH END OF TANK  
 8" LID WITH 1-22" ROUND MANHOLE COVER AT EACH END OF TANK  
 LID IS REINFORCED WITH GRADE 60 REBAR.

**TANK & LIDS:** 4000 PSI CONCRETE AT 28 DAYS

IMPRINTED ON INLET END OF TANK:

**LEGEND: FSI 1500                      STATE APPROVAL NUMBER: 01-011-23D-C4**

**WEIGHTS:** TANK ONLY 10,780  
 TANK & 4" LID 13,780  
 TANK & 8" LID 16,780

THIS SEWAGE TREATMENT RECEPTACLE HAS BEEN DESIGNED, CONSTRUCTED AND STRUCTURALLY TESTED IN ACCORDANCE WITH CHAPTER 64E-6.013, FLORIDA ADMINISTRATIVE CODE, (FAC) DATED MARCH 22, 2000

DRAWING NOT TO SCALE

**FLORIDA SEPTIC, INC**

P.O. BOX 545  
 HAWTHORNE, FLORIDA 32640  
 (800) 940-8265

**MODEL:**

4" 1500 GAL. TANK

REVISED:  
 05/01/2011

APPROVAL DATE:  
 07/30/2001